



## Town of Atherton

### **CITY COUNCIL STAFF REPORT – CONSENT AGENDA**

**TO: HONORABLE MAYOR AND CITY COUNCIL  
GEORGE RODERICKS, CITY MANAGER**

**FROM: MICHAEL KASHIWAGI, COMMUNITY SERVICES DIRECTOR**

**DATE: FEBRUARY 19, 2014**

**SUBJECT: APPROVAL OF PLANS AND SPECIFICATIONS AND  
AUTHORIZATION TO ADVERTISE FOR THE 2014 SPRING  
PATCHING PROJECT**

#### **RECOMMENDATION**

Approve the plans and specifications and authorize advertisement for bids for the 2014 Spring Patching Project, Project No.56057

#### **BACKGROUND | FINDINGS**

The FY 2013-2014 Capital Improvement Program includes funds for street maintenance. This project consists of grinding and replacing approximately 16,500 square feet of asphalt to a six-inch depth to remediate local pavement failures. This work includes all necessary traffic control and will involve grinding, sweeping, tack coating, replacing asphalt and finish rolling per Town standard specifications and special provisions.

The 2014 Spring Patching Project is budgeted for construction in FY 2013-14. The 2014 Spring Patching Project plans and specifications are ready to be advertised for construction. The project is expected to begin construction by April 2014 and to be completed by May 2014.

A list and map of the areas affected and timing of the project will be added to the Town's website and distributed via the Town's electronic news network.

#### **FISCAL IMPACT**

Parcel Tax Funds in the amount of \$100,000 are budgeted for this project in FY 2013-14. The Engineer's Estimate for the 2014 Spring Patching Project is \$100,000.

Prepared By:

Approved:

---

Michael Kashiwagi, P.E.  
Community Services Director

---

George Rodericks  
City Manager

Attachments: Attachment A – List of street locations to be patched  
Attachment A – Map of street locations to be patched

## Attachment A

2014 SPRING PATCHING - TOWN OF ATHERTON						
ID No.	ADDRESS	STREET	LENGTH	WIDTH	AREA (SF)	Notes
1	77	Logan Lane	16	4.5	72	Front Left of Driveway
2	78	Logan Lane	18	4	72	Across from
3	78	Logan Lane	21	4	84	Front of Water Meter
4	78	Logan Lane	5	5	25	Front Patch failure
5	95	Patricia Drive	35	4	140	Patricia/Austin
6	-	Stockbridge Avenue	4	4	16	~25' E/O intersection of Selby/Stockbridge
7	-	Stockbridge Avenue	17	6	102	~100' E/O intersection of Selby/Stockbridge
8	185	Stockbridge Avenue	55.5	6	333	Front of
9	179/185	Stockbridge Avenue	5	5	25	Front of
10	179	Stockbridge Avenue	25	7	175	Front of
11	179	Stockbridge Avenue	8.5	10.5	89.25	Front of
12	179	Stockbridge Avenue	19	6	114	Front of
13	180	Stockbridge Avenue	37.5	6	225	Front of
14	179	Stockbridge Avenue	16	5	80	Across from
15	185	Stockbridge Avenue	5	5	25	<b>Next to Patch #08</b>
16	185	Stockbridge Avenue	11	5	55	Across from
17	164	Stockbridge Avenue	33	6	198	Front of
18	151	Stockbridge Avenue	70	6	420	Front of
19	151	Stockbridge Avenue	96	6	576	Front of
20	190	Elena Avenue	23	4	92	Across from
21	190	Elena Avenue	25	4	100	Across from
22	180	Elena Avenue	38.5	4	154	Across from
23	180	Elena Avenue	47.5	6	285	Across from
24	172	Elena Avenue	100	4	400	Front of
25	172	Elena Avenue	43.5	4	174	Across from
26	172	Elena Avenue	60	4	240	Across from
27	168	Elena Avenue	23	4	92	Across from
28	164	Elena Avenue	19.5	4	78	Across from
29	164	Elena Avenue	24.5	4	98	Across from
30	164	Elena Avenue	23	8	184	Across from
31	164	Elena Avenue	93	6	558	Front of
32	164	Elena Avenue	9	7.5	67.5	Front of
33	164	Elena Avenue	13	7	91	Across from
34	164	Elena Avenue	11	9	99	Front of
35	164	Elena Avenue	37	10	370	Front of
36	150	Elena Avenue	60	5.5	330	Front of
37	150	Elena Avenue	23	6	138	Across from
38	1	Elena Avenue	95	6	570	Front of
39	126	Elena Avenue	44	7	308	Across from
40	126	Elena Avenue	55	6	330	Across from
41	126	Elena Avenue	34	6	204	Across from
42	102	Elena Avenue	47	5	235	Across from
43		Elena Avenue	20	10	200	At Elena/Elena Intersection
44		Elena Avenue	35	12	420	Southbound direction @ Stop sign
45		Elena Avenue	52	7	364	Westbound direction @ Stop sign
46	126	Elena Avenue	87.5	15	1312.5	Front of
47	126	Elena Avenue	114	7	798	Front of
48	126	Elena Avenue	38	7	266	50' E/O intersection
49	33	Lloyd Drive	11	16	176	Front of
50	33	Lloyd Drive	27	12	324	Front of

**Total      11884.25 SF**

## Attachment A

51	97	Virginia Lane	36	4	144	Front/Left of Driveway
52		Oak Drive	175	4	700	Front of 98 Placitas
53		Oak Drive	42	4	168	Near intersection of Placitas/ Oak Dr
54	354	Encinal Avenue	13	4	52	Across from
55	354	Encinal Avenue	22	8	176	Across from
56	348	Encinal Avenue	31	4	124	Across from
57	332	Encinal Avenue	28	6	168	Across from
58	54	Magnolia Drive	26	4	104	Front of
59		Encino Avenue	13	9	117	End of Cul de Sac
60	2	Fair Oaks Lane	21	8	168	Front of
61	2	Fair Oaks Lane	40	4.5	180	Front of
62	18	Fair Oaks Lane	15	6	90	Front of
63	18	Fair Oaks Lane	32	6	192	Front of
64	46	Fair Oaks Lane	7.5	8	60	Front of
65	46	Fair Oaks Lane	14	5.5	77	Front of
66	46	Fair Oaks Lane	8.5	5	42.5	Front of
67	2	Fair Oaks Lane	5	7	35	Across from
68	2	Fair Oaks Lane	4	4	16	Across from
69	46	Fair Oaks Lane	70	6	420	Across from
70	46	Fair Oaks Lane	17.5	5	87.5	Across from
71	62	Fair Oaks Lane	17.5	4	70	Across from
72	77	Fair Oaks Lane	7	4	28	Front of
73	77	Fair Oaks Lane	13	4	52	Front of
74	77	Fair Oaks Lane	46	4	184	Front of
75	62	Fair Oaks Lane	4	5	20	Front of
76		Ringwood Avenue	60	19	1140	Keep Clear Area in front of School DW (Not Marked)

**4615** SF

Total	16499.25 SF
-------	-------------

NO.	DATE	DESCRIPTION	BY
1		PLANS FOR BID	DGH

REGISTERED CIVIL ENGINEER	DATE
TOWN OF ATHERTON DEPARTMENT OF PUBLIC WORKS 111 ASTROD ROAD ATHERTON, CA 95727	

THIS PLAN WAS PREPARED UNDER MY DIRECTION

APPROVED BY: MICHAEL KASHIWAGI  
DIRECTOR OF PUBLIC WORKS

R.C.E. 33776

DESIGN	By	Checked
QUANTITIES	D. HUYNH	M. KASHIWAGI
SCALE: HORIZONTAL: 1"=20'		VERTICAL: 1"=20'

**TOWN OF ATHERTON**  
**DEPARTMENT OF PUBLIC WORKS**



**2014 SPRING PATCHING PROJECT**

**TITLE SHEET**

DISPERSED PRINTS BEARING ENGINEER PLAT DATES: 01/15/14

DATE PLOTTED: 01/15/14

SHEET 1 OF 1

# TOWN OF ATHERTON

## 2014 SPRING PATCHING

### PROJECT #56057





